ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

Notification, dated 9th September 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. of 2nd October 1933, for restoring Thadagani Hirekere Tank, Registered No. 1017, Shikarpur Taluk, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 500 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Thadagani Hirekere tank Registered No. 1017, Shikarpur Taluk, Shimoga District" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and not estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent of contractors profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities for restoring Thadagani Hirekere tank, Registered No. 1017 Shikarpur Taluk, Shimoga District.

Sl. No.	Items of work	Unit	Quantity	Rate in	
				Figures	Words
	Bund at R. L. 54·00 with top width of 6'				
1	Jungle clearing, scraping grass, removing rubbish and cutting grips for seat of bund.	Grade	32		
2	Earthwork to bund including watering and consolidating.	C.yds.	17,476		
3	Turfing front and rear slopes of bund ...	S.yds.	15,300		
4	Providing grade stones including chisling, painting and fixing, etc., complete.	Each	32		
5	Providing index stones including painting, etc., complete.	„	32		
6	Gauge stones including fixing well in masonry surki mortar.	„	1		
7	B. M. Stones	„	2		
8	Survey and Constructive detail stone ..	„	1		
	Constructing Sluice No. 1 at R. L. 46·75.				

Sl. No.	Items of work	Unit	Quantity	Rate in Figures	Rate in Words
5	Burnt brick in surki mortar ...	C.ft.	272		
6	Burnt stone slabs dressed, fixed 5" to 6" thick.	S.ft.	68		
7	Plastering with surki mortar ..	Sqr.	3·00		
8	Providing teak wood plug and iron rod with locking arrangements, etc.	Lump sum			
9	Cutting holes in vertical slabs ...	Lump sum			
10	Carting and fixing C. I. pipes 9" dia. in cement, etc. (pipes to be supplied departmentally).	R.ft.	24		
11	Rough stone work (revetment) ..	C.yds.	5		
	Constructing sluice No. 2 at R. L. 42·00.				
1	Earthwork cut opening the bund ..	„	53		
2	Do filling with watering and consolidation.	„	59		
3	Do excavation for foundation	„	12		
4	Metal concrete in surki mortar ...	C.ft.	121		
5	Burnt brick in surki mortar ...	„	297		
6	Burnt stone slabs dressed and fixed ...	S.ft.	79		
7	Plastering with surki mortar ...	S.yd.	3·5		
8	Providing teak wood plug and cast iron rod and with locking arrangements.	Lump sum			
9	Cutting holes in the orifice ...	Lump sum			
10	Carting and fixing C. I. pipes of 9" dia in cement (pipes to be supplied departmentally).	R.ft.	36		
11	Rough stone revetment work ...	C.yds.	9		
	Constructing sluice No. 3 at R.L. 45·70.				
1	Earthwork cut opening the bund ...	„	6		
2	Do filling in with watering and consolidation.	„	7		
3	Do excavation for foundation ...	„	10		
4	Metal concrete in surki mortar ..	C.ft.	130		
5	Burnt brick in surki mortar ...	„	285		
6	Burnt stone slabs dressed and fixed ..	S.ft.	71		
7	Plastering with surki mortar ...	Sqr.	3·00		
8	Providing teak wood plug and iron rod with locking arrangements.	Lump sum			
9	Carting and fixing C. I. Pipes of 9" dia. in cement, etc. (pipes to be supplied departmentally).	R.ft.	24		
10	Cutting holes in vertical slab ...	Lump sum			
11	Rough stone revetment work ...	C.yds.	5		
	Constructing a masonry waste weir, 82 feet long.				
1	Earthwork excavation for foundation ...	C.yds.	132		
2	Metal concrete in surki mortar ...	C.ft.	241		
3	Burnt brick in surki mortar ...	„	881		
4	Plastering with surki mortar ..	Sqr.	6·73		
5	Rough stone work with jelly packing ..	C.yds.	103		
6	Draft and approach clearing ...	Lump sum			
7	Cement concrete with thin plastering ..	C.ft.	69		

Notification dated 9th September 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M., on 3rd October 1933, for Restoring Chikkapur-Annekere Reg. No. 415 and 442, Shikarpur Taluk, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chikkapur-Annekere Regd. No. 415 and 442, Shikarpur Taluk, Shimoga District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for not-tendered and not estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent of contractors profit.

11. In all matter not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown again each item of work. Any quotation quoted at so much percentage less or more than estimated rate, will not be accepted.

Abstract quantities for Restoring Chikkapur-Annekere R. No. 415 and 442 Shikarpur Taluk, Shimoga District.

Sl. No.	Items of work	Unit	Quantity	Rate	
				In words	In figures
	Bund R. L. 57·00 Top width 6 feet.			Rs.	Rs.
1	Jungle clearing over bund and cutting grips, etc.	Lump sum			
2	Earthwork to bund with watering and tamping, etc., complete.	C.yd.	2705		
3	Gravelling over the bund with 1 mile lead ...	„	306		
4	Turfing front and rear slopes ...	Sqr.	322·36		
5	Grade stones including cutting figures and painting, etc., complete.	Each	25		
6	Index stones including cutting figures and painting, etc., complete.	„	25		
7	B. M. Stones including cutting figures and painting, etc., complete.	„	2		
8	Gauge stone including cutting figures and painting.	„	1		
9	Register No. stone including cutting figures and painting.	„	1		
10	New stone revetment with jelly backing ...	C.yd.	16		

Sl. No.	Items of work	Unit	Quantity	Rate	
				In words	In figures
	Sluice No. 1 *R. L.* 48·00 *at Cross section* 7:			Rs.	Rs.
1	Cutting the bund and refilling the same with watering and tamping.	C.yd.	39		
2	Earthwork excavation	,,	18		
3	Stone jelly surki concrete ...	C.ft.	100		
4	Brick in surki mortar	,,	782		
5	Burnt stone slabs 4" to 6" thick ..	Sq.ft.	151		
6	Plastering with surki mortar	Sqr.	4·08		
7	Carting and fixing 9" dia cast iron pipe (pipes to be supplied departmentally).	R.ft.	24		
8	Teakwood plug with iron fittings with locking arrangements, etc., complete.	Lump sum			
9	Cutting groves in orifice and gibbet slabs ...	Lump sum			
	Sluice No. 2 *R. L.* 49·00 *at Cross section* 17.				
1	Cutting bund and refilling the same with watering and tamping, etc., complete.	C.yd.	59		
2	Earthwork excavation	,,	18		
3	Stone jelly in surki concrete	C.ft.	100		
4	Brick in surki mortar	,,	714		
5	Burnt stone slabs 4" to 6" thick ...	Sq.ft.	151		
6	Plastering with surki mortar	Sqr	3·19		
7	Carting and fixing 7" dia cast iron pipe (pipes to be supplied departmentally).	R.ft.	24		
8	Teakwood plug with iron fittings and locking arrangements complete.	Lump sum			
9	Cutting groves in orifice and gibbet slabs.	Lump sum			
	Right waste-weir R. L. 52·00 *length* 40'-0".				
1	Clearing approach in front	C.yd.	218		
2	Earthwork excavation	,,	149		
3	Stone jelly concrete in surki mortar ...	C.ft.	409		
4	Burnt brick in surki mortar	,,	1,148		
5	Burnt stone slabs 4" to 6" thick dressed and fixed.	Sq.ft.	368		
6	Plastering with surki mortar ...	Sqr.	11·06		
7	New rough stone with jelly backing ...	C.yd.	170		
8	Providing joggles	Each	15		

G. SESHAGIRI RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 23rd August 1933.

The attention of the public is invited to the detailed notification calling for tenders for the maintenance work to Sivapur Tank, Mandya Taluk, published in page 1101, Part VI of the *Mysore Gazette*, dated 31st August 1933. The date up to which tenders will be received is till 12 noon on 18th September 1933.

V. V. PATANKAR,
Executive Engineer.

MEDICAL DEPARTMENTS

OFFICE OF THE EPIDEMIC DISEASES HOSPITAL, MYSORE.

Abstract Notification, dated 4th September 1933.

Sealed tenders in triplicate for the supply of Pasteurised milk for the use of the Epidemic Diseases Hospital, Mysore, for the year 1934, will be received by the undersigned on the 25th September 1933, between 8-30 and 10-30 A.M.

For details *vide* page 1127, Part VI of the *Mysore Gazette*, dated 7th September 1933.